



भेरीगंगा नगरपालिका

नगर कार्यपालिकाको कार्यालय

छिन्चु, सुर्खेत

कर्णाली प्रदेश, नेपाल

Fax ०८३- ५४०११०

Phone ०८३- ५४०१५४



मिति : २०८०/०२/०४

प.सं. :- ०७९/०८०

च नं. :

विषय :- सडक बोर्ड सडक मर्मत गर्ने तथा सामग्री खरिद सम्बन्धि सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस नगरपालिकाको तपशिलमा उल्लेखित योजनाहरु निर्माण गर्नु पर्ने र सामग्री खरिद गर्नु पर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८०/०२/१०) गते दिनको ५:०० बजे) सम्मा ईच्छुक सप्लायर्स/फर्महरुले भेरीगंगा नगरपालिकाको वेबसाईट www.bherigangamun.gov.np मा यसै पत्र साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका दर रेट मान्य हुने छैन ।

क्र.स.	कार्यक्रमको नाम	अधिकतम रकम रु.	कैफियत
१.	झिम्नी स्कुल पुर्व तर्फको सडक मर्मत	रु.४,७८,६५७.११	भ्याटसहित
२.	टपरी चुलो एकता टोल सडक मर्मत	रु.६,७०,९३१.५३	भ्याटसहित
३.	रामघाट प्रहरी चौकी अगाडिको सडक मर्मत	रु.४,७८,८९२.३८	भ्याटसहित
४.	जलवायु परिवर्तन सम्बन्धि अभिमुखीकरण तथा जोखिम पाशोचित्र निर्माण कार्यक्रम	रु.७,६२,७५०.००	भ्याटसहित
५.	जलवायु परिवर्तन सम्बन्धि सचेतानामुखी होर्डिगबोर्ड निर्माण तथा पोस्टर छपाई	रु.२,९३,८००.००	भ्याटसहित

.....
कृष्ण प्रसाद पोखरेल
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकिय अधिकृत



Government of nepal
Ministry of Federal Affairs And Local Administration
Office of The Municipal Executive
Bheriganga Municipality
Chinchu , Surkhet
Karnali Province,Nepal

कृष्ण प्रसाद पौड्याल
प्रमुख प्रशासकिय अधिकारी

Name of work :- Cross drainage & road maintenance work eastern part of jhigani school
Name of Place :- Bheriganga Municipality ward nos - 6
2079-080

Sn	Description of work	Quantity	Unit	Rate	
				In Figure	In Amount
1	Site clearance				
	Site clearance (clearing and grubbing including the cutting of trees(only if necessary) having girth of less than 30cms when measured at 1m above the ground)	12.00	M2		
2	Excavation in Roadway, Drain and foundation in Hard/BMS Soil including removal and satisfactory disposal of the materials upto a lead of 50m.	33.50	M3		
3	Stone Soiling work	4.18	M3		
4	Earthwork in filling for Roadway	52.80	M3		
5	PCC Work (1:2:4)				

	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:2:4 (1 cement : 2 sand : 4 coarse aggregate) for leveling course in foundations in all level with broken stone aggregate of size not more than 25 mm of approved quality including formwork wherever necessary, dewatering, batching, mixing, transporting, placing, compacting, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.	1.72	M3		
6	Plumb Concrete work				
	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 (1:2:4) concrete and 40% boulders/stones with dimesions all complete as per specifications, drawings and instructions of the site engineer, all complete.	15.96	M3		
7	PCC For RCC Works (1:1.5:3)	4.56	M3		
8	Reinforcement bar	679.44	Kgs		
9	Formwork	49.64	M2		
10	Hoarding Board	1	Nos		
	Sub Total Rs				
	Vat @ 13 %				
	Grand Total Rs				

Name of Firm:-

Signature :-

Stamp :-