



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल



Fax ०८३- ५४०११०
Phone ०८३- ५४०१५४

प.सं. :- ०८१/०८२
च नं.:

मिति: २०८१/०६/१६

विषय :- दररेट पेश गर्ने बारे सूचना।

श्री सम्बन्धित सरोकारवाला सबै।

प्रस्तुत विषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/०६/२२ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
१.	काल्पानीखोला देखि बसेरी हुदै धनुबाँस सडक सफाई, भेरीगंगा-१	रु. २,५०,०६८.३७/-	१. आ.व.२०८०/०८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि
२.	गुराँस तल्लो माथिल्लो भयाँग हुदै देउरालीसम्म सडक सफाई, भेरीगंगा-१	रु. ७,९७,३६८.४८/-	२. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि
३.	बसेरी देखि वाग्लेसम्म सडक सफाई, भेरीगंगा-१	रु. २,५०,२०८.९३/-	३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि

.....
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत



Bheriganga Municipality
Office Of Municipal Executives
Chinchu, Surkhet
Karnali Province

BILL OF QUANTITIES (BOQ)



कृष्ण प्रसाद पोखरेल
प्रमुख प्रशासकिय अधिकृत

Project Name: बसेरी देखि वाप्लेसम्म सडक सफाई

Location : Bheriganga Municipality -Ward No.:1, Surkhet

F/Y:2081/082

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
A	Earth work in excavation by mechanical means (Hydraulic excavator) for Roadways not exceeding 30 cm in depth but exceeding more than 1.5 m in width as well as 6 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m. levelling of road section fillings the braided channel made by run-off water as directed by Engineer-in-Charge	Sqm	11520				
1	Road section: Baseri-shalghari-ghumaune and wakle road-CH:0+000-To-CH:3+840m						
B	Earth work in excavation by mechanical means (Hydraulic excavator) for Roadways for different section of soil mass movement landslide exceeding 30 cm in depth and remove all debris and soil mass exceeding more than 4m (minimum road width) width as well as 4 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, levelling of road section fillings the braided channel made by run-off water as directed by Engineer-in-Charge.						
	Baseri-shalghari-ghumaune and wakle road different points Soil mass slide, Debris & Fallen trees clearance	Cu m	655.18				
	Supplying, fabrication, assembling, placing in position of gabion box consisting of hexagonal mesh size 100 x100mm, including rolling, cutting, weaving with 10 SWG wire, binding the gabions together and tying down the lids with binding wire 12 SWG, all complete. 1.5x1x1m Box At CH: 0+510-0+540 m	No	20				
	Rubble Packing on gabion box in proper manner including 10m lead and 1.5 m lift	Cu m	30				
	Transportation of gabion boxes to site of construction	Ls	1				
TOTAL AMOUNT WITHOUT VAT							
VAT (@13%)							
TOTAL AMOUNT WITH VAT							

Name of Firm:
Name of contractor /Representative:
Address:

Date:-
Seal of Firm:
Contact No. :