



# भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय



☎ ०८३-४४०१४४  
☎ ०८३-४४०३१०,३११,३१२  
E-mail: info@bherigangamun.gov.np  
ito.bherigangamun@gmail.com  
Website: bherigangamun.gov.np  
☎ Toll Free 18105000311

प.सं. :- २०८१/०८२  
च.न.:

प्रथम पटक प्रकाशित मिति: २०८१/१२/०४  
दोश्रो पटक प्रकाशित मिति: २०८१/१२/११

विषय : दरेट पेश गर्ने बारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत विषयमा यस भेरीगंगा नगरपालिकाको तपशिलमा उल्लेखित कार्य गर्नुपर्ने देखिएकोहुँदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/१२/१७ गते दिनको ५:०० बजे सम्ममा) ईच्छुक सप्लायर्स / फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट [www.bherigangamun.gov.np](http://www.bherigangamun.gov.np) मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दरेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।


क्र.स.	कार्यक्रमको नाम	अधिकतम रकम रु.(भ्याट सहित)	आवश्यक कागजात
१.	भेरीगंगा ९ का अधुरा सडकहरूमा पक्कि नाली निर्माण	रु.७,९९,८८१.८१/	१.आ.व.२०८०/०८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि
२.	भेरीगंगा ५ अन्तर्गत सडकहरूको स्तरोन्नति, नाली, ग्रावेल तथा नयाँ कटिग निर्माण	रु.६,०२,२६०.४६/	२.फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्णकागजातहरूको प्रतिलिपि ३.सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि

कृष्ण प्रसाद पोखरेल  
प्रमुख प्रशासकीय अधिकृत  
१९.११.१९  
कृष्ण प्रसाद पोखरेल  
प्रमुख प्रशासकीय अधिकृत

“स्वच्छ, सुन्दर र वातावरणमैत्री भेरीगंगानगर: कृषि पर्यटन र पूर्वाधारयुक्तशहर हाम्रो रहर्”



Bheriganga Municipality  
Office Of The Municipal Executive  
Chhinchu , Surkhet  
Karnali Province, Nepal  
**Bill Of Quantity**



कृष्ण प्रसाद पोखरेल  
मुख्य प्रशासकिय. अधिकृत  
E/Y-2081/082

Name Of the Project :-Bheriganga ward 9 ka adhura sadakharuma pakki nala nirman  
Location : Bheriganga Municipality Ward no :- 9

Item No.	Description Of Item Of Works	Unit	Quantity	Rate(NRS)		Amount(NRS)	Remarks
				In Figure	In Words		
A	Civil Work						
1.0	Earthwork in Excavation soft soil by machine	cu.m	335.20				
2.0	Dry stone soling / paving/ filling in foundation without sand lead upto 30 mtr	cu.m	12.00				
3.0	Cement concrete works(1:2:4) in Rounded Aggregate. It includes mixing, placing in position, vibrating, compacting, finishing, curing and all other incidents.	cu.m	8.40				
4.0	Providing and laying plumb concrete ( Boulder mixed concrete)as per drawing and specification 60% M 15 concrete and 40% boulders/stones mixer and vibrator.	cu.m	27.00				
5.0	Making wooden form work for slab and floor including supply and selection of materials fixing, nailing according to drawings, applying primer,placing separators, dismantling forms and hauling upto 30m distance.	sq.m	120.00				
6.0	Laying sub-base course of sand mixed gravel loading & transportaig mat., levelling surface & hauling upto 10m. Distance including rolling.	cu.m	81.54				
7.0	Cement concrete works(1:2:4) for RCC work(Using crushed Aggregate).	cu.m	1.20				
8.0	supplying,cutting,bending,placing in position as shown in the drawings & binding by GI wire of reinforcement steelbar for RCC works incl. haulage dist. Upto 30m.	kg	135.12				
9.0	Hoarding board flex	No.	1.00				
	Sub Total Amount NRS.						
	Vat @ 13% NRS.						
	Total Amount With Vat NRS.						
	Total Amount in Words						

Name Of the Firm/Supplier's :-  
Firms Registration No :-  
PAN/VAT Reg. No. :-

Proprietor's Name :-  
Address :-  
Phone No. :-

Signature & Stamps