



प.सं. :- २०८२/०८३

च.नं. २३१८

## भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय



☎ ०८३-५४०१५४, ५४०१११

E-mail: info@bherigangamun.gov.np  
:ito.bherigangamun@gmail.com

Website: bherigangamun.gov.np

☎ Toll Free No. : 18105000311

मिति : २०८३/०२/१२

### विषय: दर रेट पेश गर्नेबारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र (मिति २०८३/०२/१८ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट [www.bherigangamun.gov.np](http://www.bherigangamun.gov.np) मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
१	भेरीगंगा वडा नं १० का सडक ग्रावेल	रु. २,९७,०७७.२७	१. आ.व.२०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि २. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि ३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि

  
इन्जिनियर

  
सीता थापा

नि. प्रमुख प्रशासकीय अधिकृत

नि. प्रमुख प्रशासकीय अधिकृत

“समृद्ध भेरीगंगा-सुखी भेरीगंगावासी”



**Bheriganga Municipality**  
**Office Of The Municipal Executive**  
**Chhiinchu , Surkhet**  
**Karnali Province, Nepal**  
**BILL OF QUANTITY**



*(Signature)*  
**इन्जिनियर**



Name Of Project : Ward No. 10 ka sadak Gravel  
Location : Bheriganga Municipality

FY : 2082/083

Ward No :-10

Item No.	Description Of Item Of Works	Unit	Quantity	In Figure	Rate(NRS) In Words	Amount(NRS)	Remarks
1.0	Site clearance (clearing and grubbing including the cutting of trees(only if necessary) having girth of less than 30cms when measured at 1m above the ground)	M2	300.00				
	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m ( mechanical means) ( SS 907(9.4.I.B.i))	M3	1.80				
	Providing and filling stone in foundation trenches as per Drawings and Technical Specifications.( C10(6-5))	M3	0.45				
	Providing and laying of FCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications. Including formwork ( SS 2000(20.02A))	M3	0.45				
	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including formworks and pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means),( SS 2421(24.21.A.J))	M3	0.90				
	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications., RCC Grade M 20 including formwork	M3	0.68				



  
  
 दि. प्रमुख प्रशासकीय अधिकारी

2.0	Providing and laying Reinforcement Fe 500 including cutting, bending, binding, fixing in position etc. all complete in super-structure complete as per drawing and technical specifications.	Kg	55.44		
3.0	Providing and laying granular sub base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per drawing and technical specification	M3	100.73		
			Sub Total Amount NRS.		
			Vat @ 13% NRS.		
			Total Amount With Vat NRS.		
			Total Amount in Words		

Signature & Stamps

Name Of the Firm/Supplier's :-  
 Firms Registration No :-  
 PAN/VAT Reg. No. :-

Proprietor's Name :-  
 Address :-  
 Phone No. :-