



Bheriganga Municipality
Office Of Municipal Executives
Chinchu, Surkhet
Karnal Province



BILL OF QUANTITIES (BOQ)

Project Name: गुराँस तल्लो माथिल्लो भर्याग हुदै देउरालीसम्म सडक सफाई

Location : Bheriganga Municipality -Ward No.:1, Surkhet

F/Y:2081/082

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
A	Earth work in excavation by mechanical means (Hydraulic excavator) for Roadways not exceeding 30 cm in depth but exceeding more than 1.5 m in width as well as 6 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m. levelling of road section fillings the braided channel made by run-off water as directed by Engineer-in-Charge						
1	Road section kalapani-takuri-mathillo bharang-deurali CH-0+000 to CH 8+550M	Sqm	34200.00				
2	Road section: Takuri (Modghumaune)-Tallo bharang -Mathillo bharang schilo) CH.0+000-To- CH: 3+010 M	Sqm	9000.00				
3	Road section: Chain danda (tallobharang) dekhi Jana Pra. Bi school tallo bharang CH.0-000-TO-1 5KM	Sqm	8000.00				
4	Miscellaneous Road road branches and others	Sqm	3840.00				
B	Earth work in excavation by mechanical means (Hydraulic excavator) for Roadways for different section of soil mass movement landslide exceeding 30 cm in depth and remove all debries and soil mass exceeding more than 4m (minimum road width) width as well as 4 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, levelling of road section fillings the braided channel made by run-off water as directed by Engineer-in-Charge.						
1	landslide clearence along road kalapani-takuri mathillo bharang-deurali, Takuri (Modeghumaune)-Tallo bharang Mathillo bharang schilo)	Cu m	4540.94				
2	Chain danda (tallobharang) dekhi Jana Pra Bi.school tallo bharang	Cu m	589.42				


चर्चा तर्फे
कृष्ण शर्मा
इन्जिनियर-इन-चार्ज



Bheriganga Municipality
Office Of Muncpal Executives
Chhinchu, Surkhet
Karnali Province

BILL OF QUANTITIES (BOQ)



कृष्ण प्रसाद पोख्रेल
प्रशासक
प्रशासक

Project Name: गुराँस तल्लो माथिल्लो भर्याग हुदै देउरालीसम्म सडक सफाई

Location : Bheriganga Municipality -Ward No.:1, Surkhet

F/Y:2081/082

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
C	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer. 40mm thick sheet with Stand post of 40mm black pipe	no	1.00				
				TOTAL AMOUNT WITHOUT VAT			
				VAT (@13%)			
				TOTAL AMOUNT WITH VAT			

Name of Firm:

Name of contractor /Representative:

Address:

Date:-

Seal of Firm:

Contact No. :