



Bheriganga Municipality
Office Of Municipal Executives
Chhinchu, Surkhet
Karnali Province

BILL OF QUANTITIES (BOQ)


कृष्ण प्रसाद पौखेल
प्रमुख प्रशासकिय अधिकृत



Project Name: काल्पानीखोला देखि बसेरी हुदै धनुबाँस सडक सफाई

Location : Bheriganga Municipality -Ward No.:1, Surkhet

F/Y:2081/082

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
A	Earth work in excavation by mechanical means (Hydraulic excavator) for Roadways not exceeding 30 cm in depth but exceeding more than 1.5 m in width as well as 6 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m. levelling of road section fillings the braided channel made by run-off water as directed by Engineer-in-Charge						
1	Road section kalpani-Baseri-simbash-dhanbash road-CH:0+000-To-CH:6+690m	Sqm	18996.00				
B	Earth work in excavation by mechanical means (Hydraulic excavator) for Roadways for different section of soil mass movement landslide exceeding 30 cm in depth and remove all debris and soil mass exceeding more than 4m (minimum road width) width as well as 4 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, levelling of road section fillings the braided channel made by run-off water as directed by Engineer-in-Charge.						
1	kalpani-Baseri-simbash-dhanbash road landslide at different points	Cu m	1596.55				
				TOTAL AMOUNT WITHOUT VAT			
				VAT (@13%)			
				TOTAL AMOUNT WITH VAT			

Name of Firm:
Name of contractor /Representative:
Address:

Date:-
Seal of Firm:
Contact No. :