



भेरीगंगा नगरपालिका  
नगर कार्यपालिकाको कार्यालय  
छिन्चु, सुर्खेत  
कर्णाली प्रदेश, नेपाल

Fax ०८३- ५४०११०  
Phone ०८३- ५४०१५४

प.सं. :- ०८०/०८१  
च.न. :- २५९१



मिति : २०८१/०९/१०

**विषय :- सडकबोर्ड अन्तर्गतका सडक मर्मत कार्यहरूको दररेट पेश गर्ने सूचना ।**

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस नगरपालिका र सडक बोर्ड नेपालको लागत साझेदारीमा तपशिलमा उल्लेखित योजनाहरूको सामग्री सडक मर्मत निर्माण कार्य गर्नुपर्ने भएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/०९/१६ गते दिनको ५:०० बजे) सम्मा ईच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेवसाईट [www.bherigangamun.gov.np](http://www.bherigangamun.gov.np) मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका दर रेट मान्य हुने छैन ।

क्र.स.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट बाहेक)	आवश्यक कागजपत्रहरू
१.	छिन्चु डुगी खोला सडक मर्मत वडा नं.३	रु.५,७७,५५१.९८	१.आ.वा.२०७९/०८० को कर चुक्ता प्रमाणपत्र प्रतिलिपि,
२.	दोबाटो पुल देखि मूलभट्टी सडक मर्मत वडा नं.४	रु.५,५६,८४७.७१	२.फर्म सप्लायर्स र ब्यबसाय दर्ता र नबिकरण संग सम्बन्धित कागजपत्रहरूको प्रतिलिपि
३.	बबई हात्तिखाल देखि गेरुवानी सडक मर्मत वडा नं.५	रु.५,५९,६६५.६३	३.सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
४.	शिव सुन्धारा टोलदेखि लालीगुराँस टोल सडक मर्मत वडा नं.६	रु.५,७३,१२४.७६	
५.	वडा कार्यालय हुदै नवज्योति टोल जाने सडक मर्मत वडा नं.७	रु.५,६६,६१३.४५	
६.	एकता टोल सडक मर्मत वडा नं.१०	रु.५,५७,७९३.६८	

*(Handwritten signature)*

*(Handwritten signature)*  
कृष्ण प्रसाद पोख्रेल  
प्रमुख प्रशासकीय अधिकृत

कृष्ण प्रसाद पोख्रेल  
प्रमुख प्रशासकीय अधिकृत

**Bheriganga Municipality**  
Office of Municipal Executives  
Chinchu, Surkhet  
Karnali Province  
**BILL OF QUANTITIES (BOQ)**



Road Name : Babal hattihal dekhil geruwani sadak marmat  
Location of Site :- Bheriganga Municipality ward 5

5/7/2080/81

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1	Earthwork in excavation in medium type soils in foundation including 10m hauling distance and 1.8 m. lift all complete in approval of site engineer. For culvert protection wall foundation (CH-2+300 ,3+100 and 4+300) & for gabion work(CH-2+300, 3+100 and 4+800	M3	43.08				
2	Re-Gravelling work 15cm solid thickness for pot hole , reel , rut & repair at Chainage 0+200, 0+850 , 1+050 , 2+560 , 4+150 , 5+300 and 5+750	M3	9.36				
3	Supplying and soling stone in proper line and level without sand filling For wall (Ch-2+300 ,3+100 and 4+300)	M3	1.29				
4	Plain cement Concrete (PCC) for RCC works M 25(1:1.5:3) for slab/lintels/columns/beams with approved quality of cement, sand and machine crushed stone aggregate including supply of materials,mixing, laying, curing the work at least 7 days etc for (Ch-2+300 ,3+100 and 4+300)	M3	15.02				
5	TMT steel reinforcement bar of fe 500 grade including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire	kg	416.79				
6	Formwork, shuttering, centering with 19mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett all complete as per approved drawing. Specification and instruction of site engineer.	M2	42.90				
7	Procurements of Gabion box different size for gabion work(CH-2+300, 3+100 and 4+800						
a	Size(3*1*1)	No.	10.00				
b	Size(2*1*1)	No.	10.00				
8	Rubble stone packing in Gabion box	M3	50.00				
9	Hoading Board size 1.2*0.9 m2 size flex	No.	1.00				
<b>TOTAL AMOUNT WITHOUT VAT</b>							
<b>VAT (@13%)</b>							
<b>TOTAL AMOUNT WITH VAT</b>							

Name of Firm: .....  
Name of contractor /Representative: .....  
Address: .....

Date: .....  
Seal of Firm: .....  
Contact No. : .....