



प.सं. :- २०८२/०८३
च.न.:

भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय

छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल
२०७३



☎ ०८३-५४०१५४, ५४०१११
E-mail: info@bherigangamun.gov.np
:ito.bherigangamun@gmail.com
Website: bherigangamun.gov.np
☎ Toll Free No. : 18105000311

मिति : २०८२/१०/१८

विषय: दर रेट पेश गर्नुबारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८२/१०/२५ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
२.	घारीबन ठुलाखाल सडक मर्मत, भेरीगंगा-६ ।	रु. ९,९९,९६५.३२/-	१. आ.व.२०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि २. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि ३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि

मान बहादुर ठाडा
प्रमुख प्रशासकिय अधिकृत
मिति: २०८२/१०/१८

“समुद्ध भेरीगंगा-सुखी भेरीगंगावासी”

Bheriganga Municipality
Office of Municipal Executives

Chhinchu, Surkhet

Karnali Province, Nepal

Bill of Quantities



Name of Project: बाबिन ठूलाखाल सडक सभत
Location: Bheriganga 6 Surkhet

F.Y:2082/083

Item No.	Description	Unit	Quantity	Rate (In Figure)	Rate (In words)	Amount	Remarks
A	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's staff, personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract. [GCC Clause]	PS	1.00				
B	Carrying out different laboratory tests of during entire construction period as per specification and instruction of engineer	PS	1.00				
1	Earthwork Excavation in Cutting, Roadway Excavation in all types of Soil by Mechanical Means , Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer (SS 905{9.1.I.B})	Cu.m	5,533.69				
	Earthwork Excavation in Cutting,, Roadway Excavation in ordinary rock by Mechanical Means ,, Roadway Excavation in ordinary rock as per Drawing and Technical specification, including all lift and lead as per Drawing and instruction of the Engineer. (SS 905{9.1.II.B})	Cu.m	723.15				

Bill of Quantities

Name of Project: चारिन इलाखाल सडक मार्ग
Location: Bheriganga 6 Surkhet

F.Y:2082/083

Item No.	Description	Unit	Quantity	Rate (In Figure)	Rate (In words)	Amount	Remarks
3	Earthwork Excavation in Cutting, Excavation in Hard Rock (blasting prohibited), Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications, Mechanical method, lead upto 30 m (SS 905{9.1.IV.A})	Cu.m	188.64				
4	Providing and filling stone in foundation trenches as per Drawings and Technical Specifications.(C10(6-5))	Cu.m	2.25				
5	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications. Including formwork (SS 2000{20.02A})	Cu.m.	1.35				
6	Providing and laying of PCC for RCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications. Including formwork (SS 2000{20.02A})	Cu.m.	3.24				
7	Providing and laying , fitting and placing HYSD bar reinforcement as per Drawing and Technical Specifications (SS 2014{20.5})	KG	213.36				
8	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including formworks and pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means).(SS 2421(24.21.A.I))	Cu.m	15.73				

मान प्रतिष्ठान
प्रमुख प्रशासक अधिकृत



Bill of Quantities

F.Y:2082/083

Name of Project: धारिवन तृताखाल सडक मर्मत
Location: Bheriganga 6 Surkhet

Item No.	Description	Unit	Quantity	Rate (In Figure)	Rate (In words)	Amount	Remarks
12	Providing and installation of standard Project Information Board having written content as approved by the office on a 20 SWG MS Plate (1.20m*1.20m) fixed at its sides to ms angle (38mm*38mm) and supported by two MS black pipes (50mm dia) of length 2.60 m firmly embedded 600mm down into the ground with PCC M10 size(300*300*600) mm & should be maintained as such till the end of project .	Nos	1.00				
				Sub total			
				VAT @ 13%			
				• Grand Total VAT			
				Total With vat and provisional			