



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल

Fax ०८३- ५४०११०
Phone ०८३- ५४०१५४

प.सं. :- ०८१/०८२
च नं: ५८३

मिति: २०८१/०७/२९


विषय :- दररेट पेश गर्ने बारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत विषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/०८/०५ गते दिनको ४:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
१.	धारापानी टोल र सारदा जोड्ने खोलामा कल्भर्ट निर्माण तथा फूलबारी टोल कुइरे सडक मर्मत, भेरीगंगा-८	रु. ७,९८,७४४.९५/-	१. आ.व.२०८०/०८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि
२.	राताडाँडा खेलकुद मैदान निर्माण, भेरीगंगा-९	रु. ९९,८८२.९५/-	२. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि
३.	स्वास्थ्य शाखाको लागि न्यानो खोला खरिद		३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
४.	हात्तीसुडे खानेपानी ट्रान्सफर्मर खरिद र हात्तीसुडे खानेपानी मोटर स्टेबिलैजर खरिद, भेरीगंगा ४	रु. ७,४१,०२२.९५/-	


.....
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत



Bheriganga Municipality
Office Of Municipal Executives
Chinchu, Surkhet
Karnali Province



BILL OF QUANTITIES (BOQ)

Project Name: धारापानी टोल र सारदा जाइने खोलामा कल्लर्ट निर्माण र फुलबारी टोल कुइरे सडक मर्मत
Location : Bheriganga Municipality -8, Surkhet


F/Y:2081/082

कृष्ण प्रसाद पोख्रेल
मुख्य प्रशासकिय अधिकारी

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1	धारापानी टोल र सारदा जाइने खोलामा कल्लर्ट निर्माण						
1	E/w Excavation in Hard soil by Machine	M3	27.00				
2	Dry stone soling / paving / filling in foundation without sand lead up to 30 mtr.	M3	1.08				
3	Cement Concrete Works (1:2:4) in Rounded Aggregate). It includes mixing, placing in	M3	0.12				
4	Providing and laying plum concrete (Boulder mixed concrete) as per drawing and	M3	20.16				
5	Cement Concrete Works (1:1.5:3) for RCC in Superstructure (Using Crushed Aggregate)	M3	5.22				
6	Supply, Cutting, bending, placing in position as shown in the drawing & binding by GI wire	Kg	897.52				
7	Making wooden form work for slab and floor including supply and selection of materials	M2	27.00				
	फुलबारी टोल कुइरे सडक मर्मत						
1	E/w Excavation in Hard soil by Machine	M3	25.00				
2	Dry stone laying (soling)	M3	5.00				
3	Cement Concrete Works (1:2:4) for RCC in Superstructure (Using Crushed Aggregate)	M3	9.00				



Bheriganga Municipality
Office Of Municipal Executives
Chinchu, Surkhet
Karnali Province



BILL OF QUANTITIES (BOQ)

Project Name: धारापानी टोल र सारदा जाइने खोलामा कल्भर्ट निर्माण र फुलबारी टोल कुइरे सडक मर्मत
Location : Bheriganga Municipality -8, Surkhet

F/Y:2081/082

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
4	Supply, Cutting, bending, placing in position as shown in the drawing & binding by GI wire	Kg	1024.12				
5	Making wooden form work for slab and floor including supply and selection of materials	M2	6.00				
TOTAL AMOUNT WITHOUT VAT							
VAT (@13%)							
TOTAL AMOUNT WITH VAT							

Name of Firm:
Name of contractor /Representative:
Address:

Date:-
Seal of Firm:
Contact No. :