



प.सं. :- २०८२/०८३  
च.नः ३०१२

# भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय

छिन्चु, सुर्खेत  
कर्णाली प्रदेश, नेपाल  
२००३



☎ ०८३-४४०१४४, ४४०१११  
E-mail: info@bherigangamun.gov.np  
:ito.bherigangamun@gmail.c  
Website: bherigangamun.gov.np  
☎ Toll Free No. : 18105000311

मिति : २०८३/०२/१८

## विषय: दर रेट पेश गर्नेबारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र (मिति २०८३/०२/२५ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट [www.bherigangamun.gov.np](http://www.bherigangamun.gov.np) मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (म्याट सहित)	आवश्यक कागजात
१.	कैनपानि लेख झिगनी सडक नया ट्याक निर्माण, भेरीगंगा ०७	रु. २,९९,५२९.८०/-	१. आ.व.२०८१/०८२ को करचुका प्रमाणपत्रको प्रतिलिपि
२.	काउले टोल नक्ज्योति टोल सडक मर्मत, भेरीगंगा ७	रु १,९८,८८९.१३/-	२. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि
३.	समाबेसी टोल सिचाई ड्याम निर्माण, भेरीगंगा ३	रु १,९०,४८७.७६/-	३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
४.	चुरेनी ताल सिचाई पाइप तथा ड्याम निर्माण, भेरीगंगा ३	रु १,९१,४१०.५९/-	

२०८३/०२/१८  
अधिकृत

२०८३/०२/१८  
हरि बहादुर खत्री  
प्रमुख प्रशासकिय अधिकृत  
अधिकृत

“समृद्ध भेरीगंगा-सुखी भेरीगंगावासी”



Bheriganga Municipality  
Office of the Municipal Executive  
chhinchu, surkhet  
Karnali province Nepal

*[Signature]*  
महानगरपालिका  
कार्यालय



योजना को नाम : कैलापानि लेख शिविस सडक नया ट्रायाक निर्माण  
स्थान : बरिगंगा नगरपालिका वार्ड नं ०७

### Bills Of Qunatities (BOQs)

FY : 2082/083

S/N	Item of works	Units	Quantity	Rate (In Figures)	Rate (In Words)	Amount	Remarks
1	Site ceurence works: removal of bushes,shrubs,cutting grass,thatches,removal fallen trees & fillings of runn -off braided channel along the road and filling of 30cm deep ditches etc	sq m	1500				
2	Earth work in excavation for all types of soil (BMS,Gravelled mixed soil) by mechanical means(Hydraulic Excavator) for removal of debries ,land slide ,fallen trees ,topple rocks ,filling of heavy braided channel including dressing of sides and ramming of bottom, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50 m.	Cu m	1240.00				
3	Supplying, fabrication, assembling, placing in position of Heavy coated (Mesh wire 3mm Selvdge wire 3.9mm and lacing wire 2.4mm) gabion box consisting of hexagonal mesh size 100 x120 mm, including rolling, cutting, weaving with 10 SWG wire, binding the gabions together and tying down the lids with binding wire 7 SWG, all complete.						
	2XIXI	NO	9.00				

**I-SXIXI**

**4** *Packing and Filling with Rubble Stone: includes the supply of appropriate hard, durable rubble stones and the labor for their meticulous hand-packing into the gabion crates to ensure a dense fill with minimal voids, stability, and proper appearance*

No 14.00

cu m 39.00

**5** *Transportation of construction materials to the site*

Is 1.00



*(Signature)*  
 इन्डियन  
 5/10/2020  
 10:30 AM

डिप्टी. एग्जिक्यूटिव्ह. इंजीनियर  
 पब्लिक वर्क्स  
 बंगलूर

**Total Amounts Rs:**

**13% Vat Added NPRs :**

**Total Amount with VAT**

Name of Firm:

Date:

Sign:

Stamp: