



प.सं. - २०८२/०८३
च.नं: ३०९९

भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय

छिन्चु सुर्खेत
कर्णाली प्रदेश, नेपाल
२०७३



☎ ०८३-४४०१२४, ४४०१११
E-mail: info@bherigangamun.gov.np
:ito.bherigangamun@gmail.c
Website: bherigangamun.gov.np
☎ Toll Free No. : 18105000311

मिति : २०८३/०२/१८

विषय: दर रेट पेश गर्नेबारे सूचना ।


श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत विषयमा यस भेरीगंगा नगरपालिकाको तपसिलामा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र (मिति २०८३/०२/२५ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
१.	कैनपानि लेख झिगनी सडक नया ट्रायाक निर्माण, भेरीगंगा ०७	रु. २,९९,५२९.८०/-	१. आ.व.२०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि
२.	काउले टोल नक्ज्योति टोल सडक मर्मत, भेरीगंगा ७	रु १,९८,८८९.१३/-	२. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि
३.	समावेसी टोल सिचाई ड्याम निर्माण, भेरीगंगा ३	रु १,९०,४८७.७६/-	३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
४.	चुरेनी ताल सिचाई पाइप तथा ड्याम निर्माण, भेरीगंगा ३	रु १,९१.४१०.५९/-	


२०/०२/१९२
इन्जिनियर


हरि बहादुर खत्री
प्रमुख प्रशासकिय अधिकृत
प्रमुख प्रशासकिय अधिकृत

“समृद्ध भेरीगंगा-सुखी भेरीगंगावासी”



सोच्ना को नाम:- सनासेवी टोल सिचार्इ इवाय निर्माण
स्वाय र बोरोपां गणरासिका बाई नं. ०३

Bheriganga Municipality
Office of the Municipal Executive
chinchu, surkhet
Karnali province Nepal

(Signature)
सुर्खेत नगरपालिका

Bills Of Qunatities (BOQs)

F/Y : 2081/082

S/N	Item of works	Units	Quantity	Unit's Rates	Amount Rs		Remarks
					In Figures	In Word	
1	Site cearence works: removal of bushes,shrubs,cutting grass,shaches,removal of water from wells with using pumps or by manually digging temporary side drain etc	sq m	25				
2	Earth work in excavation by manually means for the foundation trenches of drain/culvert abutment / water tank foundation including dressing of sides and ramming of bottom, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 10 m.	Cu m	35				
3	Backfilling for the foundation including compaction and levelling	Cu m	7				
4	Stone soing works includings supplying laying and peveling lead 10m and lift 1.5m	Cu m	1.72225				
5	PCC of 1:2:4 cement, sand and round aggregate includings blending,mixing and placing in position and compaction ,lead 5m lift 1m	Cu m	2.62225				
6	Random Rubble stone masonry of 1:4 cement sand works for parapet wall structures includings supplying and layings of suitable stone blocks lead 10m & lift 1.5m	cu m	9.6				
7	12.5mm Plaster for the tank of 1:4 cement and sand including blending and mlxing and applying on wall 10m haul and 1.5m lift	Sq m	27				
			Total Amounts NPRs:				
			13% Vat Added NPRs :				
			Total Amounts NPRs				

Name of the firms/Supplier's :-
Firm registration No:-
PAN/VAT Reg. no:-

proprietor's name :-
address :-
Phone no:
email@address :-

signature /stamp:-

(Handwritten notes)
सुर्खेत नगरपालिका