



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल

Fax ०६३- २४०११०
Phone ०६३- २४०१२४

प.सं. :- ०६१/०६२
च नं. : २२२९

मिति: २०८२/०१/१६

विषय :- दररेट पेश गर्ने बारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुँदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८२/०१/२२ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
१.	Supply and Delivery of Construction materials, hand tools and safety tools (PPE) for LISP work in Tamata tol dekhi ward no. 8 ra 7 jodne Road Drain Construction, Bheriganga-6	रु. ५,७२,२०४.६२/-	१. आ.व. २०८०/०८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपि २. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि ३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
२.	Supply and Delivery of Construction materials, hand tools and safety tools (PPE) for LISP work in upgrading of road from chhinchu road to bhagwati pra.vi, Bheriganga-11	रु. ७,५२,४८३.२२/-	
३.	Supply and Delivery of Construction materials, hand tools and safety tools (PPE) for LISP work in Uttishpaneko Ghar dekhi Lapaneko Ghar samma Road Construction, Bheriganga-11	रु. ३,७७,९१५.७८/-	


.....
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत



Bheriganga Municipality
Office Of Municipal Executives
Chhinchu, Surkhet
Karnali Province

BILL OF QUANTITIES (BOQ)

Project Name: Supply and Delivery of Construction materials, hand tools and safety tools (PPE) for LSP work in Tamata tol dekhi ward no. 8, Bheriganga Road Drain Construction
Location : Bheriganga Municipality -6, Surkhet



कृष्ण प्रसाद पोखरेल
प्रमुख/प्रमुख अधिकारी
२०७३

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1	Cement OPC (Nepali Cement and shall be free flowing and free of lumps. It shall be supplied in the manufacturer's sealed unbroken bags or in bulk. Cement from broken bags shall not be accepted. Nepali Ordinary Portland, 53 grade Cement as per IS 269 (chemical and physical properties)	Bag	656.57				
2	Nails (2"-3") with Common nails	Kg	111.70				
3	Plywood-12mm (Commercial, comply with IS:303-Water Proof)	sqm	61.44				
4	Safety Helmets with IS/NS certified	no	10.00				
5	Safety Gloves IS/NS certified	no	10.00				
6	First Aid Kit Box with medicines IS/NS certified	Set	1.00				
7	Gumboots IS/NS certified	no	10.00				
8	Mason Hammer 1kg IS/NS certified as forged, tempered steel, length 13 cm hammer end-4cm*4 cm & edge 3 cm weight 1kg, 20mm dia hole for handle blow-4cm from the top or as per provided sample	Nos.	2.00				
9	Nail Hammer 0.5 kg IS/NS certified as forged, tempered steel, length 13 cm hammer end-4cm*4 cm & edge 3 cm weight 0.5kg, 20mm dia hole for handle blow-4cm from the top or as per provided sample	Nos.	2.00				
10	Pick (2-2.5kg) 1" * 1/4" IS/NS certified to be supplied with well seasoned wooden handle fitted wt. 2.5kgs without handle	Nos.	5.00				
11	Mason Trowel (Karni) Length-20cm, breadth at the mid-12cm and tapered gradually towards both ends, Well-seasoned wooden handle fitted well in trowel plate and anchored well at other end; steel plate thickness- 1 mm and surface should be completely smooth	Nos.	2.00				
12	Finishing Wooden Trowel Length-20cm, breadth at the mid-12cm and tapered gradually towards both ends, Well-seasoned wooden handle fitted well in trowel plate and anchored well at other end; steel plate thickness- 1 mm and surface should be completely smooth	Nos.	2.00				



Bheriganga Municipality
Office Of Municipal Executives

Chinchu, Surkhet

Karnali Province

BILL OF QUANTITIES (BOQ)

Project Name: Supply and Delivery of Construction materials, hand tools and safety tools (PPE) for USP work in Tamata tol dekhi ward no. 8 ra 7 Jodne Road Drain Construction
Location : Bheriganga Municipality -6, Surkhet

भरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
चिन्चु, सुर्खेत
२०७३

कृष्ण प्रसाद पोखरेल

F/Y:2081/0825

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRS.)		Amount (NRS.)
				In Figures	In Words	
13	Iron Pan Karai IS/NS certified	Nos.	2.00			
14	Level Pipe 6mm dia. (50m) IS/NS certified	Nos.	1.00			
15	Handsaw 16" 2 side teeth, 12mm wide	Nos.	2.00			
16	Handsaw Frame Adjustable to Hacksaw blade	Nos.	2.00			
17	Sand sieve net IS/NS certified	Nos.	1.00			
18	Plumb bob IS/NS certified	Nos.	2.00			
19	Measuring Tape - 5m IS/NS certified	Nos.	1.00			
20	Measuring Tape - 30m IS/NS certified	Nos.	1.00			
21	Mason Line rope IS/NS certified	Nos.	3.00			
TOTAL AMOUNT						
TOTAL VATABLE AMOUNT						
VAT (@13%)						
TOTAL AMOUNT WITH VAT						
TOTAL AMOUNT WITH VAT IN WORDS :						

Name of Firm:

Name of contractor /Representative:

Address:

Date:

Seal of Firm:

Contact No. :