



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल



Fax ०८३- ४४०११०
Phone ०८३- ४४०१५४

प.सं. :- ०८०/०८१
च.नं. २१९९

मिति : २०८१/०१/१०

विषय :- सडकबोर्ड अन्तर्गतका सडक मर्मत कार्यहरूको दररेट पेश गर्ने सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस नगरपालिका र सडक बोर्ड नेपालको लागत साझेदारीमा तपशिलमा उल्लेखित योजनाहरूको सामग्री सडक मर्मत निर्माण कार्य गर्नुपर्ने भएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/०१/१६ गते दिनको ५:०० बजे) सम्मा ईच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेवसाईट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका दर रेट मान्य हुने छैन ।

क्र.स.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट बाहेक)	आवश्यक कागजपत्रहरू
१.	छिन्चु डुगी खोला सडक मर्मत वडा नं.३	रु.५,७७,५५१.९८	१.आ.वा.२०७९/०८० को कर चुक्ता प्रमाणपत्र प्रतिलिपि ,
२.	दोबाटो पुल देखि मूलभट्टी सडक मर्मत वडा नं.४	रु.५,५६,८४७.७९	२.फर्म सप्लायर्स र ब्यबसाय दर्ता र नबिकरण संग सम्बन्धित कागजपत्रहरूको प्रतिलिपि
३.	बबई हात्तिखाल देखि गेरुवानी सडक मर्मत वडा नं.५	रु.५,५९,६६५.६३	३.सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
४.	शिव सुन्धारा टोलदेखि लालीगुराँस टोल सडक मर्मत वडा नं.६	रु.५,७३,१२४.७६	
५.	वडा कार्यालय हुदै नवज्योति टोल जाने सडक मर्मत वडा नं.७	रु.५,६६,६१३.४५	
६.	एकता टोल सडक मर्मत वडा नं.१०	रु.५,५७,७९३.६८	

(Handwritten signature)

.....
कृष्ण प्रसाद पोख्रेल
प्रमुख प्रशासकीय अधिकृत



Bheriganga Municipality
Office of Municipal Executives
Chhinchu, Surkhet
Karnali Province

[Handwritten Signature]

BILL OF QUANTITIES (BOQ)

Road Name : Ekattatole sadak Marmat
Location of Site :- Bheriganga Municipality ward 10

F/Y:2080/81

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1	Earthwork in excavation in medium type soils in foundation for drain repair at (Chainage 0+020 to 0+050, 1+150 to 0+200, 0+560 to 0+570, 1+160 to 1+174) including 10m hauling distance and 1.8 m. lift all complete in approval of site engineer.	M3	23.56				
2	Re-Gravelling work 15cm solid thickness for pot hole, reel, rut & repair at Chainage 0+100, 0+150, 0+550, 1+560, 1+950, and 2+050	M3	2.81				
3	Supplying and soling stone in proper line and level without sand filling at (Chainage 0+020 to 0+050, 1+150 to 0+200, 0+560 to 0+570, 1+160 to 1+174)	M3	10.71				
4	PCC work with(1:2:4) crushed aggregate at (Chainage 0+020 to 0+050, 1+150 to 0+200, 0+560 to 0+570, 1+160 to 1+174)	M3	10.71				
5	Providing and laying plumb Concrete(Boulder mixed concrete)as per drawing and specification 60% M15 concrete and 40% boulders/stones Manually at (Chainage 0+020 to 0+050, 1+150 to 0+200, 0+560 to 0+570, 1+160 to 1+178)	M3	25.70				
6	Formwork, shuttering, centering with 19mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett all complete as per approved drawing, Specification and instruction of site engineer.	M2	58.91				
7	Hoarding Board size 1.2*0.9 m2 size flex	N0.	1.00				
						TOTAL AMOUNT WITHOUT VAT	
						VAT (@13%)	
						TOTAL AMOUNT WITH VAT	

Name of Firm:
Name of contractor /Representative:
Address:

Date:
Seal of Firm:
Contact No. :