



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल



Fax ०८३- ५४०११०
Phone ०८३- ५४०१५४

प.सं. :- ०८०/०८१
च.नं. :- २२४४

मिति : २०८१/०१/१४

विषय :- सडकबोर्ड अन्तर्गतका सडक मर्मत कार्यहरूको दररेट पेश गर्ने सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत विषयमा यस नगरपालिका र सडक बोर्ड नेपालको लागत साझेदारीमा तपशिलमा उल्लेखित योजनाहरूको सडक मर्मत निर्माण कार्य गर्नुपर्ने भएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/०१/२० गते दिनको ५:०० बजे) सम्मा ईच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेवसाईट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका दर रेट मान्य हुने छैन, दर्ता गर्ने ।

क्र.स.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट बाहेक)	आवश्यक कागजपत्रहरू
१.	गुराँसे देखि वडा कार्यालय जाने सडक मर्मत वडा नं.१	रु.५,९९,४१४.४१	१.आ.वा.२०७९/०८० को कर चुक्ता प्रमाणपत्र प्रतिलिपि, २.फर्म सप्लायर्स र ब्यबसाय दर्ता र नबिकरण संग सम्बन्धित कागजपत्रहरूको प्रतिलिपि ३.सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
२.	मोहटि सडक मर्मत वडा नं.२	रु.६,००,९२८.१२	
३.	छिन्चु जाजरकोट सडकको बिजय टोल देखि वडा कार्यालय जाने सडक मर्मत वडा नं.८	रु.५,५६,६४९.१९	
४.	प्रगतितोल नाच्ने खोला पुल बाट महतारा टोल जाने सडक मर्मत वडा नं.९	रु.५,५७,००१.९८	
५.	ईलाका प्रहरी कार्यालय देखि सिम्ताली चोक सम्मको सडक मर्मत वडा नं.१२	रु.५,५२,४२३.९०	

१/१४

मान बहादुर ठाडा

नि. प्रमुख प्रशासकीय अधिकृत

नि. प्रमुख प्रशासकीय अधिकृत



Bheriganga Municipality
Office Of Municipal Executives
Chinchu, Surkhet
Karnali Province

बि. प्रमुख प्रशासिक अधिकारी

BILL OF QUANTITIES (BOQ)

Road Name : Chinchu jajarkot sadak ko bijaya tole dekhi woda karyalaya jaane sadak marmat
Location of Site :- Bheriganga Municipality ward 08

F/Y:2080/81

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1	Earth work in excavation soft soil including satisfactory disposal upto 1.5m lift and 10m lead as instructed by site incharge	Cu.m	150.00				
2	Stone soiling without sand filling on footing/floor including ramming as specification as instructed by site incharge	Cu.m	9.60				
3	PCC Work(1:2:4) with crushed aggregate for Floor and Foundation Level	Cu.m	6.00				
4	PCC for RCC 1:1.5:3 crushed aggregate work in superstructure,deek,slab,beams including collection of materials & a leade of 30 m.	Cu.m	1.60				
5	Supply, Cutting, bending, placing in position as shown in the drawing & binding by GI wire of reinforcement steelbar for RCC works incl. haulage dist. upto 30m	Kg	170.68				
6	Providing and laying plum concrete (Boulder mixed concrete) as per drawing and specification 60 % M15 concrete and 40 % boulders/stones Manually	Cu.m	18.80				
7	Preparation of formwork,fixing and removing all complete including 30m lead in floor, slab	Sq.m	128.00				
8	Laying sub-base course of sand mixed gravel including loading & transporting mat., levelling surface & hauling up to 10m. Distance including rolling 15cm solid thickness.	Cu.m	48.00				
9	Hoarding Board size 1.2*0.9 m size	no	1.00				
TOTAL AMOUNT WITHOUT VAT							
VAT (@13%)							
TOTAL AMOUNT WITH VAT							

Name of Firm:
Name of contractor/Representative:
Address:
Date:
Seal of Firm:
Contact No.: