



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल



Fax ०८३- ५४०११०
Phone ०८३- ५४०१५४

प.सं. :- ०८०/०८१
च.नं. :- ४२४२

मिति : २०८१/०१/१४


विषय :- सडकबोर्ड अन्तर्गतका सडक मर्मत कार्यहरूको दररेट पेश गर्ने सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत विषयमा यस नगरपालिका र सडक बोर्ड नेपालको लागत साझेदारीमा तपशिलमा उल्लेखित योजनाहरूको सडक मर्मत निर्माण कार्य गर्नुपर्ने भएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८१/०१/२० गते दिनको ५:०० बजे) सम्मा ईच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाईट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका दर रेट मान्य हुने छैन, दर्ता गर्ने ।

| क्र.स. | कार्यक्रमको नाम | अधिकतम रकम रु. (भ्याट बाहेक) | आवश्यक कागजपत्रहरू |
|--------|---|---------------------------------|---|
| १. | गुराँसे देखि वडा कार्यालय जाने सडक मर्मत वडा नं.१ | रु.५,९९,४१४.४९ | १.आ.वा.२०७९/०८० को कर चुक्ता प्रमाणपत्र प्रतिलिपि, २.फर्म सप्लायर्स र ब्यबसाय दर्ता र नबिकरण संग सम्बन्धित कागजपत्रहरूको प्रतिलिपि ३.सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि |
| २. | मोहटि सडक मर्मत वडा नं.२ | रु.६,००,९२८.१२ | |
| ३. | छिन्चु जाजरकोट सडकको बिजय टोल देखि वडा कार्यालय जाने सडक मर्मत वडा नं.८ | रु.५,५६,६४९.१९ | |
| ४. | प्रगतिटोल नाच्ने खोला पुल बाट महतारा टोल जाने सडक मर्मत वडा नं.९ | रु.५,५७,००९.९८ | |
| ५. | ईलाका प्रहरी कार्यालय देखि सिम्ताली चोक सम्मको सडक मर्मत वडा नं.१२ | रु.५,५२,४२३.९० | |



मान बहादुर ठाडा
नि. प्रमुख प्रशासकीय अधिकृत

नि. प्रमुख प्रशासकीय अधिकृत



Bheriganga Municipality
Office Of Municipal Executives
Chhinchu, Surkhet
Karnali Province
BILL OF QUANTITIES (BOQ)

नि प्रमुख प्रशासकिय अधिकारी
Date: _____
Signature: _____



F/Y:2080/81

Road Name : Pragati tol Nachnekhola Pul bata mahatara tol jane sadak marmat
Location of Site :- Bheriganga Municipality ward 09

| S.N. | Description of Items | Unit | Quantity | Unit Rate (NRs.) | | Amount (NRs.) | Remarks |
|---------------------------------|---|------|----------|------------------|----------|---------------|---------|
| | | | | In Figures | In Words | | |
| 1 | Earth work in excavation soft soil including satisfactory disposal upto 1.5m lift and 10m lead as instructed by site incharge Ch 0+000-1+000 | Cu.m | 17.28 | | | | |
| 2 | Stone soiling without sand filling on footing/floor including ramming as specification as instructed by site incharge Ch 0+000-1+000 | Cu.m | 2.16 | | | | |
| 3 | PCC Work(1:2:4) with crushed aggregate for Floor and Foundation Level Ch 0+000-1+000 | Cu.m | 1.44 | | | | |
| 4 | Providing and laying plum concrete (Boulder mixed concrete) as per drawing and specification 60 % M15 concrye and 40 % boulders/stones using concrete mixer and vibrator Ch 0+000-1+000 | Cu.m | 31.68 | | | | |
| 5 | PCC for RCC 1:1.5:3 crushed aggregate work in superstructure,deek,slab,beams including collection of materials & a leads of 30 m.Ch 0+000-1+000 | Cu.m | 4.68 | | | | |
| 6 | Supply ,Cutting, bending, placing in position as shown in the drawing & binding by GI wire of reinforcement steelbar for RCC works incl. haulage dist. upto 30m Ch 0+000-1+000 | Kg | 831.31 | | | | |
| 7 | Preparation of formwork,fixing and removing all complete including 30m lead In floor, slab Ch 0+000-1+000 | Sq.m | 12.00 | | | | |
| 8 | Back filling with approved materials obtain from borrow pits excluding excavation. Ch 0+000-1+000 | Cu.m | 60.00 | | | | |
| 9 | Hoarding Board size 1.2*0.9 m size flex | no | 1.00 | | | | |
| TOTAL AMOUNT WITHOUT VAT | | | | | | | |
| VAT (@13%) | | | | | | | |
| TOTAL AMOUNT WITH VAT | | | | | | | |

Name of Firm:
Name of contractor /Representative:
Date:
Seal of Firm:
Address:
Contact No. :